


UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Dylan Johnson Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Mon Jan 19 10:30:15 Page: 1



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.


Job	Truss	Truss Type	Qty	Ply	
26010397	R2	Monopitch	23	1	Job Reference (optional)

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Dylan Johnson

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Mon Jan 19 10:30:16

Page: 1

ID:F9nUnlKkkwCDTaEzlpjPHpztrBb-0il27KTd3aLkcWM6HSTxqJf1F1_cdyq3GJU?VWztqfr



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.80	Vert(LL)	-0.43	16-18	>899	240	MT20 244/190
Snow (Ps/Pg)	7.7/10.0	Lumber DOL	1.15	BC	0.95	Vert(CT)	-0.86	16-18	>447	180	M18AHS 186/179
TCDL	10.0	Rep Stress Incr	YES	WB	0.76	Horz(CT)	0.08	26	n/a	n/a	
BCLL	0.0 *	Code	IBC2018/TPI2014	Matrix-MSH							
BCDL	10.0										
Weight: 324 lb FT = 20%											

LUMBER		WEBS	5-20=-1617/542, 4-20=-2642/738, 1-23=-88/695, 3-22=-1534/443, 4-22=-26/464, 5-19=-1213/4525, 7-19=-1033/388, 7-18=-823/3069, 8-18=-603/272, 8-16=-237/910, 10-14=-1165/319, 11-14=-16/554, 11-26=-3187/855, 12-26=-1080/295	12) This truss is designed in accordance with the 2018 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
TOP CHORD	2x6 SP No.2 *Except* 2-6:2x6 SP No.1			13) This truss has been designed for a moving concentrated load of 250.0lb live located at all mid panels and at all panel points along the Bottom Chord, nonconcurrent with any other live loads.
BOT CHORD	2x6 SP No.2			14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
WEBS	2x4 SP No.3 *Except* 5-19,7-18,8-16,10-14,11-13:2x4 SP No.1			
OTHERS	2x6 SP No.2			
BRACING		NOTES		LOAD CASE(S) Standard
TOP CHORD	Structural wood sheathing directly applied or 3-0-8 oc purlins, except end verticals.	1) Unbalanced roof live loads have been considered for this design.		
BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.	2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=55ft; Cat. II; Exp B; Enclosed; Gable Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left exposed ; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60		
WEBS	1 Row at midpt 4-20, 3-22, 11-13	3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=10.0 psf; Ps=7.7 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; Min. flat roof snow load governs.		
REACTIONS	(lb/size) 20=1784/0-5-8, (min. 0-3-1), 24=221/0-5-8, (min. 0-1-8), 26=723/0-5-8, (min. 0-1-8)	4) Roof design snow load has been reduced to account for slope.		
	Max Horiz 24=72 (LC 13)	5) Unbalanced snow loads have been considered for this design.		
	Max Uplift 20=-390 (LC 16), 24=-41 (LC 12), 26=-158 (LC 12)	6) All plates are MT20 plates unless otherwise indicated.		
	Max Grav 20=2577 (LC 2), 24=409 (LC 48), 26=1045 (LC 2)	7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.		
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.		
TOP CHORD	1-24=-259/107, 1-2=-734/117, 2-3=-731/118, 3-4=-321/1083, 4-5=-1018/3659, 5-6=-806/176, 6-7=-805/179, 7-27=-3756/986, 8-27=-3748/988, 8-9=-4620/1226, 9-10=-4607/1227, 10-11=-3475/923, 11-12=-382/103, 12-26=-182/851	9) Bearing at joint(s) 24, 26 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.		
BOT CHORD	23-29=-205/735, 22-29=-202/737, 22-30=-1067/242, 21-30=-1064/243, 20-21=-1063/243, 20-31=-3686/960, 19-31=-3683/963, 19-32=-224/793, 18-32=-221/796, 17-18=-1025/3735, 17-33=-1024/3736, 16-33=-1022/3738, 16-34=-1254/4610, 15-34=-1252/4610, 14-15=-1252/4612, 14-35=-940/3474, 26-35=-939/3475	10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 41 lb uplift at joint 24, 390 lb uplift at joint 20 and 158 lb uplift at joint 26.		
		11) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 20.		

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCE and Truss Plate Institute.




Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
26010397	R3	Monopitch	12	1	

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Dylan Johnson

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Mon Jan 19 10:30:17

Page: 1

ID:XZszbYgAsP?ievF2kMNCvltznK-UvsQKgTGquTbEgxlR_AmWFP5RMIMLJDuzEY1yztqfq



Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.89	Vert(LL)	-1.16	12-13	>432	240	MT20	244/190
Snow (Ps/Pg)	7.7/10.0	Lumber DOL	1.15	BC	0.76	Vert(CT)	-2.31	12-13	>216	180	M18AHS	186/179
TCDL	10.0	Rep Stress Incr	YES	WB	1.00	Horz(CT)	0.23	19	n/a	n/a		
BCLL	0.0*	Code	IBC2018/TPI2014	Matrix-MSH								
BCDL	10.0											
											Weight: 272 lb	FT = 20%

- LUMBER**
TOP CHORD 2x6 SP No.2
BOT CHORD 2x6 SP SS
WEBS 2x4 SP No.3 *Except*
7-9,16-1,15-2,13-4,12-5,10-6:2x4 SP No.1
OTHERS 2x6 SP No.2
- BRACING**
TOP CHORD Structural wood sheathing directly applied or 1-9-4 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 5-5-4 oc bracing.
WEBS 1 Row at midpt 7-9, 6-10
- REACTIONS** (lb/size) 17=922/0-5-8, (min. 0-1-9), 19=906/0-5-8, (min. 0-1-8)
Max Horiz 17=52 (LC 13)
Max Uplift 17=-197 (LC 12), 19=-198 (LC 16)
Max Grav 17=1332 (LC 2), 19=1308 (LC 2)
- FORCES** (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-1244/373, 1-2=-4864/1322, 2-3=-7761/2098, 3-4=-7752/2099, 4-20=-8746/2359, 5-20=-8735/2360, 5-6=-7866/2122, 6-7=-5054/1359, 7-8=-473/130, 8-19=-267/1134
BOT CHORD 16-22=-1372/4837, 15-22=-1370/4839, 14-15=-2141/7742, 14-23=-2140/7743, 13-23=-2139/7744, 13-24=-2394/8738, 12-24=-2392/8740, 12-25=-2148/7877, 11-25=-2146/7877, 10-11=-2146/7879, 10-26=-1375/5061, 19-26=-1375/5062
WEBS 7-19=-4699/1270, 2-16=-981/368, 1-16=-1267/4738, 2-15=-792/2963, 4-15=-549/239, 4-13=-266/1043, 5-12=-974/250, 6-12=0/369, 6-10=-2873/785, 7-10=-133/876, 8-19=-1350/369
- NOTES**
1) Unbalanced roof live loads have been considered for this design.
- 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=55ft; Cat. II; Exp B; Enclosed; Gable Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left exposed ; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=10.0 psf; Ps=7.7 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; Min. flat roof snow load governs.
4) Roof design snow load has been reduced to account for slope.
5) Unbalanced snow loads have been considered for this design.
6) All plates are MT20 plates unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Bearing at joint(s) 17, 19 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 197 lb uplift at joint 17 and 198 lb uplift at joint 19.
11) This truss is designed in accordance with the 2018 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
12) This truss has been designed for a moving concentrated load of 250.0lb live located at all mid panels and at all panel points along the Bottom Chord, nonconcurrent with any other live loads.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- LOAD CASE(S)** Standard


Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
26010397	R4	Monopitch Structural Gable	1	1	

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Dylan Johnson

Run: 8.83 S Apr 11 2025 Print: 8.830 S Apr 11 2025 MiTek Industries, Inc. Mon Jan 19 10:30:18

Page: 1

ID:gyqtlhGznzdzUCKQS4IZF8ztqlG-y5QpY0UuaCbSrQWUPtVPvkog8rm05y7MjdzaOztqfp




Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	-0.10	35-36	>999	240	MT20	244/190
Snow (Ps/Pg)	7.7/10.0	Lumber DOL	1.15	BC	0.50	Vert(CT)	-0.16	35-36	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.38	Horz(CT)	0.01	33	n/a	n/a		
BCLL	0.0 *	Code	IBC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 251 lb	FT = 20%

LUMBER		2) Wind: ASCE 7-16; Vult=115mph (3-second gust)	15) This truss has been designed for a moving concentrated load of 250.0lb live located at all mid panels and at all panel points along the Bottom Chord, nonconcurrent with any other live loads.
TOP CHORD	2x6 SP No.2	Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=55ft; Cat. II; Exp B; Enclosed; Gable Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left exposed ; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60	
BOT CHORD	2x6 SP No.2		
WEBS	2x4 SP No.3		
OTHERS	2x4 SP No.3 *Except* 19-37:2x6 SP No.2		
BRACING		3) Truss designed for wind loads in the plane of the truss only.	
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.	4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=10.0 psf; Ps=7.7 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; Min. flat roof snow load governs.	
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing, Except: 10-0-0 oc bracing: 35-36,33-35.	5) Roof design snow load has been reduced to account for slope.	
WEBS	1 Row at midpt 2-33	6) Unbalanced snow loads have been considered for this design.	
REACTIONS		7) All plates are 2x5 () MT20 unless otherwise indicated.	
(lb) - Max Horiz	36=52 (LC 11)	8) Gable studs spaced at 2-0-0 oc.	
Max Uplift	All uplift 100 (lb) or less at joint(s) 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 36, 37 except 32=-767 (LC 39), 33=-164 (LC 14)	9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.	
Max Grav	All reactions 250 (lb) or less at joint (s) 19, 32, 37 except 20=345 (LC 69), 21=309 (LC 68), 22=316 (LC 67), 23=315 (LC 66), 24=313 (LC 65), 25=319 (LC 64), 26=310 (LC 63), 27=316 (LC 62), 28=314 (LC 61), 29=315 (LC 60), 30=312 (LC 59), 31=328 (LC 58), 33=1255 (LC 39), 36=471 (LC 54)	10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.	
FORCES		11) Bearing at joint(s) 36, 19, 37, 20, 21, 22, 23, 24 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.	
(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 36, 19, 25, 37, 20, 21, 22, 23, 24, 26, 27, 28, 29, 30, 31 except (jt=lb) 33=164, 32=766.	
TOP CHORD	1-36=-369/138, 1-2=-1036/251	13) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 19, 25, 37, 33, 20, 21, 22, 23, 24, 26, 27, 28, 29, 30, 31, 32.	
BOT CHORD	35-39=-307/1026, 34-39=-305/1029, 33-34=-304/1030	14) This truss is designed in accordance with the 2018 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.	
WEBS	1-35=-232/926, 4-33=-553/253, 2-33=-1084/313, 5-32=-97/253		
NOTES			
1) Unbalanced roof live loads have been considered for this design.			

This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
26010397	R5	Monopitch	1	1	




Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	I/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.57	Vert(LL)	-0.10	5-6	>999	240	MT20
Snow (Ps/Pg)	7.7/10.0	Lumber DOL	1.15	BC	0.61	Vert(CT)	-0.16	5-6	>999	180	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.81	Horz(CT)	0.02	8	n/a	n/a	
BCLL	0.0*	Code	IBC2018/TPI2014	Matrix-MSH							
BCDL	10.0										Weight: 100 lb FT = 20%

- LUMBER**
 TOP CHORD 2x6 SP No.2
 BOT CHORD 2x6 SP No.2
 WEBS 2x4 SP No.3
 OTHERS 2x6 SP No.2
BRACING
 TOP CHORD Structural wood sheathing directly applied or 5-5-14 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 7-8-6 oc bracing.
 WEBS 1 Row at midpt 2-4
REACTIONS (lb/size) 6=405/0-5-8, (min. 0-1-8), 8=385/0-5-8, (min. 0-1-8)
 Max Horiz 6=42 (LC 13)
 Max Uplift 6=-86 (LC 12), 8=-85 (LC 16)
 Max Grav 6=585 (LC 2), 8=555 (LC 2)
FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-6=-500/360, 1-9=-1476/858, 2-9=-1467/861, 2-3=-252/145, 3-8=-152/454
 BOT CHORD 5-11=-886/1464, 8-11=-885/1465
 WEBS 1-5=-775/1347, 2-5=-123/271, 2-8=-1249/750, 3-8=-578/349
- 5) Unbalanced snow loads have been considered for this design.
 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3'-06"-00 tall by 2'-00"-00 wide will fit between the bottom chord and any other members.
 8) Bearing at joint(s) 6, 8 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 86 lb uplift at joint 6 and 85 lb uplift at joint 8.
 10) This truss is designed in accordance with the 2018 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 11) This truss has been designed for a moving concentrated load of 250.0lb live located at all mid panels and at all panel points along the Bottom Chord, nonconcurrent with any other live loads.
 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

- NOTES**
 1) Unbalanced roof live loads have been considered for this design.
 2) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=55ft; Cat. II; Exp B; Enclosed; Gable Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left exposed ; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=10.0 psf; Ps=7.7 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; Min. flat roof snow load governs.
 4) Roof design snow load has been reduced to account for slope.
- LOAD CASE(S)** Standard

Job	Truss	Truss Type	Qty	Ply	Job Reference (optional)
26010397	R6	Monopitch Supported Gable	1	1	



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.04	Vert(LL)	n/a	-	n/a	999	MT20
Snow (Ps/Pg)	7.7/10.0	Lumber DOL	1.15	BC	0.08	Vert(TL)	n/a	-	n/a	999	244/190
TCDL	10.0	Rep Stress Incr	YES	WB	0.04	Horiz(TL)	0.00	10	n/a	n/a	
BCLL	0.0*	Code	IBC2018/TPI2014	Matrix-MSH							
BCDL	10.0										Weight: 91 lb FT = 20%

LUMBER		
TOP CHORD	2x6 SP No.2	
BOT CHORD	2x6 SP No.2	
WEBS	2x4 SP No.3 *Except* 19-10:2x6 SP No.2	
OTHERS	2x4 SP No.3	
BRACING		
TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.	
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.	
REACTIONS		
	All bearings 14-6-8.	
(lb) - Max Horiz	18=42 (LC 13)	
Max Uplift	All uplift 100 (lb) or less at joint(s) 10, 11, 12, 13, 14, 15, 16, 17, 18	
Max Grav	All reactions 250 (lb) or less at joint (s) except 10=279 (LC 56), 11=333 (LC 55), 12=331 (LC 54), 13=330 (LC 53), 14=331 (LC 52), 15=330 (LC 51), 16=334 (LC 50), 17=315 (LC 49), 18=258 (LC 48)	
FORCES		
(lb) - Max. Comp./Max. Ten.	- All forces 250 (lb) or less except when shown.	

- NOTES**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=55ft; Cat. II; Exp B; Enclosed; Gable Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Corner (3) zone; cantilever left exposed ; end vertical left exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=10.0 psf; Ps=7.7 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10; Min. flat roof snow load governs.
 - Roof design snow load has been reduced to account for slope.

- Unbalanced snow loads have been considered for this design.
 - All plates are 2x5 (||) MT20 unless otherwise indicated.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
 - Bearing at joint(s) 18, 10, 11, 12, 13, 14, 15, 16, 17 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint (s) 18, 10, 11, 12, 13, 14, 15, 16, 17.
 - Non Standard bearing condition. Review required.
 - This truss is designed in accordance with the 2018 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - This truss has been designed for a moving concentrated load of 250.0lb live located at all mid panels and at all panel points along the Bottom Chord, nonconcurrent with any other live loads.
- LOAD CASE(S)** Standard